

Storing SIPs

Once the delivery truck is unloaded, use blocking to keep panels elevated and flat. Panels will be delivered wrapped in 7 mil heat shrink plastic. If for any reason the panels are not wrapped when they arrive, make sure to tarp them to protect them from precipitation and keep panels elevated above standing water. Keep spline material and 2nd top plate material dry and flat. Dimensional lumber to be used for sills, plates, and splines should also be kept dry. Wet lumber will swell and become difficult to fit into panel recesses. If necessary, store construction sealant and expanding foam sealant in a heated enclosure to keep it above the minimum storage and working temperature. (50 degrees F).



PorterSIPs are shrink wrapped at the factory for weather protection.